

L. D. Strobel Co., Inc. 1022 Shary Circle, Unit 9 Concord, CA 94518 925-686-3241 925-686-3350 (Fax)

Contact: Danton Sherrod / Construction Manager

Date: May 30, 2024

Customer: Marin Emergency Radio Authority.

1400 Fifth Ave. San Rafael, CA.

Job Name: Site Alarming

Job Address: Coyote Peak / Mill Valley / My Tamalpais / Muir Beach / OTA

Skyview Terrace / Stewart Point / Tomales / Wolfback Ridge.

Description: 1. Provide & install Cat5 alarming circuits up to 100ft from existing punch down to

Generator & ILC at nine MERA communication sites.

2. Generator Alarms to include High Temp/ Run / Oil level/ MAN & AUTO/ Batt / Low

Fuel \ Comm fail.

3. ATS Alarm to include Power Fail / Power In Use / Power Available / Power in Use 4. OTA & Wolfback Ridge Provide & Install HVAC alarm / Door Sensor & Smoke

Detectors. Provide alarm circuit back to punch down block. 5. Provide & install D Ring cable support every 18".

6. Install to include testing & Gen & ATS alarm matrix.

Exclusions: Price assumes alarm path to Gen & ILC has been provided by MERA GC.

Price is based on Prevailing Wadge Rates.

Price is based on MERA staff availability & on site for 8hrs per day. MERA on site staff to assist with alarm testing day of installation.

Quote is based on that all MERA provided / installed equipment is alarm capable. Quote is based on a single MOB fee. Additional trips will be subject to a re mob fee.

Pricing:

Labor......\$25,460.00

Materials.....\$3,378.00

Per diem & Lodging.....\$3,240.00

Total......\$32,078.00

All material is to be as specified. All work to be completed in a professional manner according to standard practic alteration or deviation from the above specifications involving extra costs will be executed upon written orders.  Authorized Signature
Note: We may withdraw this proposal if not accepted within 30 days.  Acceptance of Proposal The above prices, specifications and conditions are satisfactory and are hereby accepted. You are authorized to do the work as specified. Payments will be made as outlined above.
Date of Acceptance

Signature \_\_\_\_\_